BRUHAT BENGALURU MAHANAGARA PALIKE

Name of Work:-Drilling of borewells and providing water supply facilities to ward No 01,02,03 & 04.

Modified Schudule-B

Sl No	Description of work	Unit	Qty	Rate	Rs in Words
1	Geophysical investigation at site for sinking borewells for supplying drinking water to the habitation either through the Hand Pump MWS or P.W.S.S. by vertical electrical sounding by adopting Venner or Schlumbergers's method. including econnaissance survey of geological formation. Geophysical investigation of existing ground water in the vicinity, its quality, quantity and acceptability of the users. indicating the location of the site. recommended depth of casing pipe required to seal the top unconsolidated formation including an extra depth of 1.0 metre in consolidated formation for proper seating of casing pipe. depth of drilling required to cover full depth of aquifer proposed to be tapped. probable yield and other information required including transportation of instruments and accessories to work site. engaging technical personal and labour required etc. NOTE: 1) Additional rate on item 1&2 is allowed for drilling in over burden and fixing Casing pipes beyond 20 M (for fixing Casing pipes only) a) Above 20 M and upto 30 M - 15%. b) Above 30 M - 30% (Measurement of overburden is restricted to the depth of casing pipe fixed excluding initial depth of 20M and projection above ground level). 2) A sum of Rs. 100/- is to be deducted for Dry Borewell towards yield test and as	Each BW	10.00	5929.37	Rupees Five Thousand Nine Hundred Twenty Nine And Paise Thirty Seven Only
2	Sinking of Borewell of 165mm dia clear using super fast hydraulic rig of capacity 300 PSIG & above 1100 CMF & above in all strata including over burdern upto 20 m. Fixing of casing pipes. collars and cap with necessary cutting. threading and welding including transportation of rig and supporting vehicle. crew charges and cost of consumables etc., complete including yield testing at the final depth with a minimumworking of compressor for one hour (Excluding cost of casing pipes,collars, cap etc., complete) and as per the directions of the Engineer-in-charge of the work	Rmtr	500.00	334.47	Rupees Three Hundred Thirty Four And Paise Forty Seven Only
3	50-100mtrs(PWD SR 2021-22 Vol-V Page No.151, Item No.1.2)	Rmtr	500.00	419.82	Rupees Four Hundred Nineteen And Paise Eighty Two Only
4	100-150mtrs (PWD SR 2021-22 Vol-V Page No.151, Item No.1.3)	Rmtr	500.00	446.35	Rupees Four Hundred Forty Six And Paise Thirty Five Only
5	150-200mtrs (PWD SR 2021-22 Vol-V Page No.151, Item No.1.4)	Rmtr	500.00	517.85	Rupees Five Hundred Seventeen And Paise Eighty Five Only
6	200-250mtrs (PWD SR 2021-22 Vol-V Page No.151, Item No.1.5)	Rmtr	500.00	607.82	Rupees Six Hundred Seven And Paise Eighty Two Only
7	250-300mtrs (PWD SR 2021-22 Vol-V Page No.151, Item No.1.6)	Rmtr	500.00	643.57	Rupees Six Hundred Forty Three And Paise Fifty Seven Only
8	300-350mtrs (PWD SR 2021-22 Vol-V Page No.151, Item No.1.7)	Rmtr	495.00	715.08	Rupees Seven Hundred Fifteen And Paise Eight Only
9	Supply of ISI mark 175mm nominal bore.plain and steel casing pipe grade of steel Fe 410 of wall thickness conforming to IS 4270-2001 and latest ammendments. electrical resistance welded steel tubes. material and conforming to IS 1387-1993 and manufactured by basic open hearth electric or basic oxygen process in random length of 5-7m both ends.threaded conforming to IS 554-1985 one end fixed with socket conforming to IS 4270 2001 and the other end with screwed pipes all shall be responsibaly free from defects. The tubes shall be responsible straight end should be with ISI marking weighing 25.10kg/m. prices include Collar-Medium duty and as per the directions of the Engineer-in-charge of the work	Rmtr	568.00	2229.43	Rupees Two Thousand Two Hundred Twenty Nine And Paise Forty Three Only
10	PVC pipes of 10 Kg/cm2 for 200mm and as per the directions of the Engineer-in-charge of the work	m	112.50	1393.46	Rupees One Thousand Three Hundred Ninety Three And Paise Forty Six Only
	Above 125%	m	41.50	1393.46	Rupees One Thousand Three Hundred Ninety Three And Paise Forty Six Only

11	Providing and laying at site of work MS casing caps as per IS 1239 (partII) 1982 with all latest amendments if any for any dia. The thickness of plate for covering one end shall be 3mm (minimum). The dimensions of caps and colars shall be strictly as per IS 1239 (Part-II) 1982 with all amendments including cost of material and labour charges for fixing, if any etc. complete with all lead and lifts and as directed by the Engineer in charge and as per the directions of the Engineer-in-charge of the work	Each	10.00	189.15	Rupees One Hundred Eighty Nine And Paise Fifteen Only
12	Fabricating supplying and mounting MS box of 16 SWG suitable for floor /wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clA with necessary cable entry pipe with gland and box should be finished with 7tanks treatment with powder coated paint and finally finished with approved colour etc., complete and as per the directions of the Engineer-in-charge of the work	Sq.cm	176000.00	0.40	Rupees And Paise Forty Only
13	Supply and delivery at site wrought middle steel (galvanized) 50 mm dia GI Union confirming to IS 1239-II, 1991 with latest amendments if any and as per the directions of the Engineer-in-charge of the work	Each	8.00	252.58	Rupees Two Hundred Fifty Two And Paise Fifty Eight Only
14	Supply and delivery at site wrought middle steel (galvanized) 50 mm dia GI hexagonal nipple confirming to IS 1239-II, 1991 with latest amendments if any and as per the directions of the Engineer-in-charge of the work	Each	24.00	201.84	Rupees Two Hundred One And Paise Eighty Four Only
15	Supply and delivery at site wrought middle steel (galvanized) 50 mm dia GI elbow confirming to IS 1239-II, 1991 with latest amendments if any for and as per the directions of the Engineer-in-charge of the work	Each	24.00	252.58	Rupees Two Hundred Fifty Two And Paise Fifty Eight Only
16	Labour charges for Erection, Electrification and commissioning of Pump sets, including aligning and balancing of all items including supply and erection of two pair of supporting clamps, bore well caps, cable clips and water tight gland cable protectors, bolts, nuts, valve and gauges,tools and equipments etc., involved in the job as per specifications, with necessary tests as per specifications, with testing of as per instructions and as per the directions of the Engineer-in-charge of the work	Job	8.00	7093.10	Rupees Seven Thousand Ninety Three And Paise Ten Only
17	Labour charges for erection of outdoor type panel board and meter boardunits with all necessary materials and labour, tools and equipments including providing cement concrete foundation bed etc., complete as per specification, with testing of as per instructions and as per the directions of the Engineer-in-charge of the work	Job	8.00	1557.02	Rupees One Thousand Five Hundred Fifty Seven And Paise Two Only
18	Supplying of 1.1KV LT UG cable XPLE or heat resistant PVC Insulated PVC eatruded inner sheath armoured UG LT cable as per IS -1554(Part-1) or IS-7098 Part-1,Armouring strip thickness in average +5% and resistivity 14ohms/kms(max) as per IS -3975 4 core 16sqmm and as per the directions of the Engineer-in-charge of the work	Rmtr	333.00	157.28	Rupees One Hundred Fifty Seven And Paise Twenty Eight Only
19	Labour charges for laying of 1.1 KV class UG cable in existing trench GI pipe/ stone pipe / on wall/ on pole as required 6 sqmm to 16 sqmm and as per the directions of the Engineer-in-charge of the work	Rmtr	333.00	12.46	Rupees Twelve And Paise Forty Six Only
20	Digging of trench of 0.6m deep x 0.50 mtr wide refilling the trench to the required ground level and consolidating etc., complete cutting road surfaces and as per the directions of the Engineer-in-charge of the work	Mtr	324.00	85.98	Rupees Eighty Five And Paise Ninety Eight Only
21	Supplying and fixing of class A GI pipe on pole/wall/drain crossing with necessary clamping arrangements for UG cable of 1.1 KV class 40mm and as per the directions of the Engineer-in-charge of the work	Mtr	32.00	351.25	Rupees Three Hundred Fifty One And Paise Twenty Five Only
22	Earthing: Supplying and fixing and wiring earth electrode for grounding circuits IC cutouts and other equipments on the meter board in the pit. The pits should be filled up with equal proportion of salt and charcoal 150mm around the pipe to complete depth. The connection from the pipe to the conduits etc. is to established through GI wire of sizes as per clause 7.3.3 of IS 732 using 12mm bolts, nuts, washers and check nuts, the pipe shall have 16 through holes of 12mm dia and as per the directions of the Engineer-in-charge of the work	Job	8.00	4325.06	Rupees Four Thousand Three Hundred Twenty Five And Paise Six Only

	oviding,Supplying and fixing suitable for 1.1 KV class UG cable filled ith necessary bitumen/insulating compound complete with terminals, cl s,bolts,nuts and washers etc. with necessary materials and labour tools and equipments as per instructions of engineer incharge of work. 3x6 Sqm and as per the directions of the Engineer-in-charge of the work	Each	8.00	593.98	Rupees Five Hundred Ninety Three And Paise Ninety Eight Only
24	Supply and fixing polished wood board made of not less than 15mm thick plank on both sides of not more than 2 pieces and fixing the same to the wall using tapered inverted wooden plugs screws 20" x 20" x 2.5" and as per the directions of the Engineer-in-charge of the work	Nos	8.00	330.28	Rupees Three Hundred Thirty And Paise Twenty Eight Only
25	Providing,supplying to work site, Submersible Pump Set of 150mm dia suitable for bore well and confirming to IS 8034-2000;3Phase, SS Bowl & Impeller with Low volt Motor as per specifications,as per necessary ammendments and instructions of engineer incharge of work. 17.50 HP - 120 LPM @ 308 m = 26 STG Outlet Dia - 2.00" and as per the directions of the Engineer-in-charge of the work	Each	8.00	82792.71	Rupees Eighty Two Thousand Seven Hundred Ninety Two And Paise Seventy One Only
26	Supply and delivery of galvanized mild steel tubes of 6mtr standard length heavy duty (C Class) as per IS 1239 (Part-I) 1990 with latest amendments with ISI Mark (one end fitted with Heavy Duty collar and other end fitted with protective cover) and as per the directions of the Engineer-in-charge of the work	Each	342.00	3517.72	Rupees Three Thousand Five Hundred Seventeen And Paise Seventy Two Only
27	Supplying and drawing 3 core flat PVC sheathed submersible pump cable manufactured with electrolytic grade copper with flexible copper with low resistance conductor confirming to13:8130-1984 and virgin grade PVC insulation and powder coating extruded PVC sheathed suitable for working voltage upto 1100 V as per IS-694:2010. 3C x 6 mm2 and as per the directions of the Engineer-in-charge of the work	Mtr	4836.00	253.74	Rupees Two Hundred Fifty Three And Paise Seventy Four Only
28	Supplying fully automatic star-delta starter unit push button type with suitable wires, 3 contactors, one adjustable thermal timer mounted on a common base plate held in steel enclosure for use on 400/440 V 3 phase and wired after fixing to the existing wooden board for motor Above 12.5 HP upto 25 HP and as per the directions of the Engineer-in-charge of the work	Nos	8.00	9059.04	Rupees Nine Thousand Fifty Nine And Paise Four Only
29	Supply and delivery at site of brand new best make gate valve as per IS 778/1984 with ISI Mark and as per its latest amendments Size 50 mm and as per the directions of the Engineer-in-charge of the work	Each	8.00	1441.69	Rupees One Thousand Four Hundred Forty One And Paise Sixty Nine Only
30	Supply and delivery at site of brand new best make non-return valve as per IS 778/1984 with ISI Mark and as per its latest amendments Size 50 mm and as per the directions of the Engineer-in-charge of the work	Each	8.00	1470.52	Rupees One Thousand Four Hundred Seventy And Paise Fifty Two Only
31	Supply and delivery at site delivery of best indigenous brand new MCB (Miniature Circuit Breakers) of required capacity as per IS 88228/1978 and its latest amendments and with ISI Mark of 6/10/16/20/25/40 Amps with scalable box. and as per the directions of the Engineer-in-charge of the work.per 3 Poles	EACH	8.00	1441.69	Rupees One Thousand Four Hundred Forty One And Paise Sixty Nine Only
32	Earth work excavation for pipelines/cables by Manual means upto 600 mm trench width, as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and	Cum	1528.38	542.07	Rupees Five Hundred Forty Two And Paise Seven Only
33	Providing and installing at site of work 6 Kg/m2: 63mm(weight of pipe - 0.662 kg) P.V.C. pipes including cost of pipes and specials and labour, including lowering into trenches, laying true to line, level and perfect linking at joints leak proof including jointing of approved type with all labour charges and all lift charges, handling charges including encasing the pipe around to a depth not less than 15 cms with gravel or selected earth available from the excavation etc. complete and as per the directions of the Engineer-in-charge of the work	mtr	2911.20	176.46	Rupees One Hundred Seventy Six And Paise Forty Six Only
34	Refilling available earth around trenches/pipelines, cables in layers not exceeding 20 cms in depth, compacting each deposited layer by ramming after watering with a lead upto 50 m , and lift upto 1.5 m. Including cost of all labour complete as per specifications and as per the directions of the Engineer-in-charge of the work	Cum	1528.38	140.71	Rupees One Hundred Forty And Paise Seventy One Only

E1	Supplying, laying and jointing HDPE pipes of specified grade andconforming to IS 4984-2016 with latest ammendments and conveying to work site including loading and unloading at both destinations and rolling and lowering into trenches, laying true to line and jointing of pipes and specials with electrofusion welding, giving hydraulic test as per relevant ISS with all lead and lifts including encasing the pipe alround to a depth of not less than 15 cms. with soft gravel or selected earth availablefrom the excation, testing and commissioning. The rate is exclusive of required specials and fittings wherever necessary like saddle Tee, stub ends, flanged sets, bedns, reducers etc. complete (Contractor will make his own arrangements for procuring water for testing) etc. Note: Upto 110mm dia Coil shall be used.For Grade PE80 PN16.0 :(I NO-5.1, P no-123 BWSSB SR)	M	366.10	275.78	Rupees Two Hundred Seventy Five And Paise Seventy Eight Only
E2	Sinking of Borewell of 165mm dia clear using super fast hydraulic rig of capacity 300 PSIG & above 1100 CMF & above in all strata including over burdern upto 20 m. Fixing of casing pipes, collars and cap with necessary cutting, threading and welding including transportation of rig and supporting vehicle, crew charges and cost of consumables etc., complete including yield testing at the final depth with a minimumworking of compressor for one hour (Excluding cost of casing pipes,collars, cap etc., complete) and as per the directions of the Engineer-in-charge of the work 350.00-400.00M	M	61.00	804.27	Rupees Eight Hundred Four And Paise Twenty Seven Only

Executive Engineer
Yelahanka Division
BBMP

Executive Engineer
Bruhat Bengaluru Mahanagara Palike
Yelahanka, Division